Terry's Plumbing Service

License #: CFC046012

2401 15th Street
Sarasota, Florida 34237

(941) 955-5362

https://www.terrysplumbingserviceinc.com/plumbing-service

service@terrysplumbinginc.com

Terry's Plumbing Service Estimate 100313

SENT

Gulfstream Towers

(941) 955-7534

Service Address:

33 S Gulfstream Avenue
Sarasota, FL 34236

Billing address:

33 S Gulfstream Avenue
Sarasota, FL 34236

Service Location: Gulfstream Towers

Service Location Address: 33 S Gulfstream Avenue Sarasota, FL 34236

Service Members: GEORGE STILWELL

Date: Jul 30, 2025

Expiration Date: Aug 29, 2025

Status: Sent

PIPE HANGER REPLACEMENTS IN PARKING GARAGE AREA (REVISED 8-12-2025)

** Before project to begin, please have cars moved from work area **
** Project does not need to be consecutive days **

- Remove old hangers and rods
- Supply and install stainless steel ring style (teardrop) hangers with 3/8" stainless steel rods, rod couplings and anchors
- Installing:
25 - 4" hangers
119 - 3" hangers
6 - 2" hangers
80 - 1-1/2" hangers
75 - 1-1/4" hangers

** Price is based on 2-men for 3 days, if additional time is required to complete project, additional labor will be added to total **
** IF using Galvanize 3/8" rods and Zinc rod couplings: MINUS $460.00 off total**
** Labor rate for 2-men is $260.00 per hour ** (No minimum)**
** Please allow 3 - 5 days for delivery of hangers and rods **

$11,560.00
(Payment as follows: $5,000.00 down / $6,560.00 upon completion of 3 days)

Item	Quantity	Amount
QUOTE	1	$11,560.00

Item	Quantity	Amount
Hanger Replacement		

Thank you for your business!

Total	**$11,560.00**
Amount Paid	**$0.00**
Amount Due	**$11,560.00**

Contract

Exclusions: Any additional work not listed on this proposal will be an additional charge.

Terms: 100 % balance due upon completion of work unless otherwise notated.

Disclaimer: I understand and accept the estimate, specifications and conditions. I have authority to authorize the estimate. Terry's Plumbing, Service Inc. is authorized to do the work as specified. The seller will retain title to all equipment and parts until payment in full is received and can be repossessed in the event of non-payment. Unless otherwise notated, payment is due in full upon completion of work. A finance charge of 18% will be added to account on past due amount. The customer agrees to pay all attorney fees, court fees, and all collection cost of past due account. Customer shall carry fire, tornado and other necessary insurance. Customer shall assume risk of loss or damage to equipment after the equipment is set in place on the job. Any modifications, amendments or changes will be in writing and signed by both parties. It is the customer's responsibility to meet permit inspector for all inspections. If inspection fails due to customer not being at job location when inspector is there, the customer agrees to pay re-inspection fees.

This estimate is valid for 30 days from date.

Signature

Date